




## INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification <sup>7</sup> : B29C 55/18, 55/08		#5	A2	(11) International Publication Number: WO 00/69615
(21) International Application Number: PCT/US00/13287		(43) International Publication Date: 23 November 2000 (23.11.00)		
(22) International Filing Date: 15 May 2000 (15.05.00)		(81) Designated States: AE, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CR, CU, CZ, DE, DK, DM, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, TZ, UA, UG, UZ, VN, YU, ZA, ZW, ARIPO patent (GH, GM, KE, LS, MW, SD, SL, SZ, TZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).		
(30) Priority Data: 09/312,103 14 May 1999 (14.05.99) US		Published Without international search report and to be republished upon receipt of that report.		
(71) Applicant: EXXON CHEMICAL PATENTS, INC. [US/US]; 5200 Bayway Drive, Baytown, TX 77520 (US).				
(72) Inventors: BRADY, Kevin, A.; 317 Claire Lane, Cary, IL 60013 (US). MACKAY, John, H.; 910 Bristol Trail Road, Lake Zurich, IL 60047 (US).				
(74) Agent: ELLIOT, Douglas, H.; Suite 1500, 3040 Post Oak Boulevard, Houston, TX 77056 (US).				

(54) Title: PROCESS FOR ADJUSTING WVTR AND OTHER PROPERTIES OF A POLYOLEFIN FILM

## (57) Abstract

A process for rendering films, film composites, and articles made therefrom less resistant to passage of water vapor by passing a filled precursor film or film composite through the nip of interdigitating grooved rollers. The films or film composites are generally formed using a precursor film of a film forming polyolefin or polyolefin blend, with a relatively high filler loading and optionally an elastomer. A process is disclosed for making diapers or other disposable items where a relatively high water vapor is coupled with a resistance to liquid strikethrough. In one embodiment of the invention, the interdigitating grooved rollers are maintained in a temperature range of from about 91 °F to about 159 °F.



**FOR THE PURPOSES OF INFORMATION ONLY**

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL	Albania	ES	Spain	LS	Lesotho	SI	Slovenia
AM	Armenia	FI	Finland	LT	Lithuania	SK	Slovakia
AT	Austria	FR	France	LU	Luxembourg	SN	Senegal
AU	Australia	GA	Gabon	LV	Latvia	SZ	Swaziland
AZ	Azerbaijan	GB	United Kingdom	MC	Monaco	TD	Chad
BA	Bosnia and Herzegovina	GE	Georgia	MD	Republic of Moldova	TG	Togo
BB	Barbados	GH	Ghana	MG	Madagascar	TJ	Tajikistan
BE	Belgium	GN	Guinea	MK	The former Yugoslav Republic of Macedonia	TM	Turkmenistan
BF	Burkina Faso	GR	Greece	ML	Mali	TR	Turkey
BG	Bulgaria	HU	Hungary	MN	Mongolia	TT	Trinidad and Tobago
BJ	Benin	IE	Ireland	MR	Mauritania	UA	Ukraine
BR	Brazil	IL	Israel	MW	Malawi	UG	Uganda
BY	Belarus	IS	Iceland	MX	Mexico	US	United States of America
CA	Canada	IT	Italy	NE	Niger	UZ	Uzbekistan
CF	Central African Republic	JP	Japan	NL	Netherlands	VN	Viet Nam
CG	Congo	KE	Kenya	NO	Norway	YU	Yugoslavia
CH	Switzerland	KG	Kyrgyzstan	NZ	New Zealand	ZW	Zimbabwe
CI	Côte d'Ivoire	KP	Democratic People's Republic of Korea	PL	Poland		
CM	Cameroon	KR	Republic of Korea	PT	Portugal		
CN	China	KZ	Kazakstan	RO	Romania		
CU	Cuba	LC	Saint Lucia	RU	Russian Federation		
CZ	Czech Republic	LI	Liechtenstein	SD	Sudan		
DE	Germany	LK	Sri Lanka	SE	Sweden		
DK	Denmark	LR	Liberia	SG	Singapore		
EE	Estonia						

## PROCESS FOR ADJUSTING WVTR AND OTHER PROPERTIES OF A POLYOLEFIN FILM

### 5 RELATED APPLICATIONS

This application is a continuation-in-part application of co-pending U.S. Application No. 08/690,136 filed July 31, 1996. This application claims the benefit of U.S. Provisional Application Nos. 60/104,452 and 60/104,455 filed October 16, 1998 and U.S. Provisional Application Nos. 60/104,948 and  
10 60/104,985 filed October 20, 1998.

### TECHNICAL FIELD

This invention relates generally a process of adjusting the water vapor transmission/porosity of films and film composites, while maintaining general  
15 resistance to liquid transmission (striethrough). More specifically this invention is directed towards a process for producing films, film composites, and articles made therefrom, that are made permeable to water vapor, by passing them through interdigitating grooved rollers. Also, more specifically this invention is directed toward filled polypropylene films having excellent Water Vapor Transmission  
20 Rates (WVTR), high tear strength, high dart impact strength, and a soft feel.

### BACKGROUND OF THE INVENTION

Polyolefin films which are rendered more permeable to water vapor using filler loading and orientation are known.

25 Such films or film composites are said to be more breathable, that is to have improved, increased permeability to water vapors, while maintaining a resistance to liquid striethrough (defined herein). Uses of such films or film composites include on a diaper the permeability of which may permit the passage of moisture vapor and air, while substantially preventing the passage of liquid.  
30 The advantages of such a film used in a diaper are that after the wearer voids, the liquid is generally retained, while much of the liquid vapor can escape decreasing the "wet feeling", and lowering the possibility of uncomfortable diaper rash.

Interdigitating grooved rollers have been used to orient either certain films or exclusively nonwoven laminates. Use of such rollers to orient (i.e., stretch) a film or nonwoven substrate is typically referred to as a ring-rolling process. To increase the water vapor transmission rate ("WVTR") of a film stretched by a ring-rolling process, it has been customary to increase either the filler loading in the formulation or the depth of engagement of the interdigitating grooves. However, both of these processing options have technical limitations on their ability to increase the WVTR of a film. Also, each option can potentially have negative effects on the physical properties of the stretched film, if a specific film's tolerance for filler loading and/or groove engagement depth is exceeded. Accordingly, there is a need for alternative means for increasing the WVTR, without negatively effecting a film's physical properties.

Also, it is desired for many applications of breathable films, such as disposable diapers, adult incontinent products, and feminine hygiene devices, to produce a film appearance that can provide the manufacturer and consumers of such products visual evidence of those products made of breathable films versus those made from non-breathable films.

U.S. Patent No. 4,472,328, assigned to Mitsubishi Chemical Industries, Ltd., suggests a breathable polyolefin film prepared from a polyolefin/filler composition having from 20 percent to 80 percent by weight of a filler such as a surface treated calcium carbonate. A liquid or waxy hydrocarbon polymer elastomer such as a hydroxyl-terminated liquid polybutadiene was purported to produce a precursor film that could be mono-axially or biaxially stretched to make a film breathable. The breathable film described by Mitsubishi is also described in Great Britain Patent No.2,115,702, assigned to Kao Corporation. The Kao patent further describes a disposable diaper prepared with a breathable film as disclosed by the Mitsubishi patent. The breathable film is used as a backing for the diaper to contain liquid.

U.S. Patent No. 4,350,655 by W. H. Hoge, assigned to Biax Fiber Film, describes a porous polyolefin synthetic paper film containing at least 50 percent by weight of a coated inorganic filler. The film composition was comprised of from 50 to 70 weight percent of an inorganic filler material coated with a silicon

or titanium fatty acid ester. To produce such a film product, Hoge teaches to cool the disclosed film substrate down into a temperature range of 10°C to 70°C (i.e., 50°F to 158°F, respectively) prior to stretching the film. Hoge refers to such a process as a "cold stretching" the film. Hoge also indicates that such cold stretching helps develop the desired void volume and surface ruptures per unit area so that weight percent resin content of the final product ranges from 0.18 to about 0.32 g/cm<sup>3</sup>. Moreover, the precursor film is formed without the addition of an elastomer and contains an inorganic filler surface coated with either a Si or Ti fatty acid ester. Some of the resulting films were stated to be both vapor and liquid permeable, however, at least one film (Example 3) was stated to be permeable to air.

US 4,777,073 (Sheth) suggests a breathable film produced by stretching of a precursor film prepared from a polyolefin/filler composition. Sheth suggests that the permeability and strength, especially tear strength are improved by melt embossing the precursor film with a patterned melt embossing roller and stretching the film to impart a pattern of different film thickness having greater permeability within the areas of reduced thickness compared to the areas of greater thickness.

Most of these techniques require that a film or film composite be rendered breathable, regardless of the technique but generally through tentering (for transverse direction or TD orientation, and differential speeds of two rollers for machine direction or MD orientation), in a separate operation, prior to final construction of the end-use article, for instance the diaper, leading to expensive double processing or more expensive transport of the film rendered less dense by the tentering operation.

Among the most serious limitations, is the extreme difficulty in producing a cost effective lamination between polypropylene nonwoven materials and polyethylene breathable films. Traditional glue, hotmelt, or meltblown adhesive techniques can be used, but require the additional cost and process complexity of the gluing system and the adhesive. The preferred method of heat lamination was generally not reliable because the difference in melting points of the polypropylene nonwoven (~161°C) and the polyethylene film (~125°C). To

achieve an adequate lamination bond strength between the two materials, pin holes or damage to the breathable film at the film/nonwoven bond site resulted.

Previous polypropylene breathable films, while having lamination advantages over polyethylene films, have been deficient in a number of other performance categories. Film oriented by traditional Machine Direction  
5 Orientation, Transverse Direction Orientation, or Biaxial Orientation (all known in the art) have had very low tear and impact strength.

For those product applications which do not laminate the breathable film directly to a nonwoven, or which by nature of the product, a hot melt type  
10 adhesive gluing system is desirable (such as a breathable film diaper backsheet), polypropylene breathable film will be more resistant to glue burn through of the film. Thus, the use of a polypropylene breathable film helps to achieve product integrity. Also, the use of higher temperature glues, as well as a lower quantity of glue is required for adequate product bond strength.

15 Accordingly, there is need for an improved ring-rolling process and/or polymer film composition that can increase the WVTR of a film, without significantly diminishing the film's physical properties. There is also a commercial need for a polypropylene microporous breathable film with high tear and impact strengths well as a soft feel. Also, there is need for films produced by  
20 such an improved process to be readily distinguishable as breathable films.

### SUMMARY OF THE INVENTION

According to one aspect of the present invention, there is provided a process for producing a film having a WVTR greater than 200 g/m<sup>2</sup>/day at 38°C and 90%  
25 relative humidity comprising a polyolefin and a filler, said process comprising: a) extruding a precursor film from said polyolefin blend comprising said first and  
said second polymer compositions and said filler, said filler concentration being in a range of from about 16.5 to about 71.5 wt.%; and b) passing said precursor film  
between at least one pair of interdigitating grooved rollers, said rollers being  
30 maintained in a temperature range from about 91°F to about 159°F, so that said film is heated to produce said film having a WVTR greater than 200 g/m<sup>2</sup>/day at  
38 °C and 90% relative humidity.

According to another aspect of the present invention, there is provided a process for producing a film having a WVTR of at least 200 g/m<sup>2</sup>/day at 38°C and 90% relative humidity comprising a polyolefin blend, said polyolefin blend having at least a first and a second polymer composition, and a filler, said process comprising: a) extruding a precursor film from said polyolefin blend comprising said first and said second polymer compositions and said filler, said filler concentration being in a range of from about 16.5 to about 71.5 wt.%, wherein, i) said first polymer composition is a polypropylene and ii) said second polymer composition is selected from the group consisting of elastomers, plastomers, styrenic block copolymers, ethylene-maleic anhydride copolymers, ethylene ethyl acetate, and combinations thereof; and b) passing said precursor film between at least one pair of interdigitating grooved rollers so that said film has at least: i) a WVTR in a range of from about 200 g/m<sup>2</sup>/day to about 10,000 g/m<sup>2</sup>/day at 38°C and 90% relative humidity, ii) a dart drop impact in a range of from about 100 grams to about 300 grams, and iii) an elongation selected from the group consisting of machine direction, transverse direction and combinations thereof in a range of from about 150% to about 550%.

### BRIEF DESCRIPTION OF THE DRAWINGS

The foregoing aspects, features and advantages of the present invention will become clearer and more fully understood when the following detailed description, and appended claims are read in conjunction with the accompanying drawings, in which is a schematic drawing of an embodiment of our invention for imparting breathability to a film or film composite:

Figure 1 is a schematic view of a process for converting a precursor film (and optionally other layers) into a film with greater WVTR;

Figure 2 illustrates a cross-sectional view of the interdigitating grooved rollers of Figure 1, taken along the lines 2-2;

Figure 3 illustrates an enlarged view of area 3 from Figure 2 showing several interdigitating teeth from the grooved rollers; and

Figure 4 shows how a film is stretched with interdigitating rollers.

## DETAILED DESCRIPTION OF PREFERRED EMBODIMENTS

We have discovered that certain polyolefin films and film composites can be processed to have greater water vapor transmission rates, relatively low liquid strikethrough, while maintaining film integrity, by using certain film forming  
5 formulations and techniques and passing the film, the film composite and/or the finished fabricated disposable article, through a nip of at least one pair of interdigitating grooved rollers.

We have discovered that applying heat to interdigitating grooved rollers results in a substantial improvement in orientation effectiveness (WVTR  
10 increases), and imparts a 3 dimensionality to the film which differentiates it from other breathable film. In addition a new control is provided for the adjustment of film breathability, i.e. rather than require a formulation change, or adjustment to the depth of activation, to control WVTR levels, roller temperature merely needs to be adjusted. As can be seen from the following examples, with all other factors  
15 constant, an increase in interdigitating roll temperature from 70°F to 140°F, increases WVTR from 1900 g/m<sup>2</sup>/day to 4100 g/m<sup>2</sup>/day.

We have also discovered that producing a precursor film from a polypropylene and filler (preferably calcium carbonate) blend, then incrementally orienting the film with interdigitating grooved rollers in the machine direction, or  
20 the transverse direction, or both, will yield a reasonably soft film (to the touch) with good impact and tear strength. It was further discovered that by adding a minority amount of low density polyethylene, extrusion processability was greatly improved. It was further discovered that the addition of a minority amount of an elastomer or plastomer improved impact and tear strength further, and contributed  
25 to an even softer film "feel". Impact strength is approximately double that of previously available polypropylene breathable films stretched by conventional techniques, other than interdigitating grooved rollers. MD tear strength is more than triple that of Machine Direction Oriented and Biaxial Oriented polypropylene  
30 breathable films. TD tear strength is greater than triple that of Transverse Direction Oriented and Biaxial Oriented polypropylene breathable films. Because stretching such film blends by interdigitating grooved rollers was expected to produce film with substantially similar physical properties as films with stretched



with conventional stretching techniques, such dramatic improvements in physical properties proved most surprising.

In certain embodiments of the invention, a polyolefin film or film composite comprises at least one layer of a disposable article and is rendered  
5 breathable by passing the film, film composite or fabricated article through interdigitating grooved rollers. The film, film composite or fabricated article will have either a single layer or multilayer construction and the polyolefin/filler combination can be co-extruded, laminated or blended with other polymers or polymer based fabricated articles.

10 In an embodiment of the invention, a film ("precursor film") is made, utilizing a polyolefin or a polyolefin blend with a relatively higher filler loading, generally including embossing a pattern thereupon, such that its subsequent manipulation, either by itself, in a film composite or as a part of a disposable article, will render the film breathable (hereinafter defined as water vapor  
15 permeable, within certain limits of WVTR, while maintaining a certain level of liquid impermeability) while maintaining a minimum level of physical properties, elongation/tensile strength being of most importance. The manipulation of the film, film composite, and/or fabricated disposable article includes passing all or parts of the film, film composite, and/or fabricated disposable article through a  
20 grooved roller and/or interdigitating grooved rollers, at a rate sufficient to develop a minimum level of breathability to the film or film portion of the article, at a commercial and economical rate.

The tear strength, elasticity, and softness of a film prepared from the polyolefin/filler composition may be improved by addition of small amounts of an  
25 olefinic elastomer.

The WVTR desired is above 100 g/m<sup>2</sup>/day @ 38°C, 90% RH (Relative Humidity), preferably above 200 g/m<sup>2</sup>/day, and can be easily greater than 1000 g/m<sup>2</sup>/day.

### 30 Introduction

This invention concerns all polyolefin/filler based breathable films that have high WVTR, the ability to be drawn down to low basis weights, and methods

for making same. Particularly useful in these films and methods are impact copolymer polypropylene. The process is also effective for all polyolefin materials. The term impact copolymer herein refers to a homopolymer matrix having a small amount of an ethylene/propylene copolymer dispersed throughout.

5           This invention further includes certain polyolefins, their conversion into fabricated articles such as films, articles made from such films, and applications in which such articles having high WVTR combined with good physical properties are desirable. The resulting films, and film composites, (including co-extruded and laminated films) have combinations of properties rendering them superior and  
10           unique to films or film composites previously available. The films disclosed herein are particularly well suited for use in producing certain classes of high WVTR films, consumer and industrial articles using the films in combination with for instance, polymeric woven or non-woven materials. Such consumer articles include, but are not limited to diapers, adult incontinence devices, feminine  
15           hygiene articles, medical and surgical gowns, medical drapes, industrial apparel, building products such as "house-wrap", roofing components, and the like made using one or more of the films disclosed herein. Additionally the films of the present invention may also be used in metallized films with a high WVTR, according to the disclosure of U.S. Patent No. 5,055,338, fully incorporated herein  
20           for purposes of U.S. patent practice.

          High WVTR films, high WVTR film composites, and disposable articles made therefrom of our invention, are produced from a precursor film that is prepared from a polymer composition that comprises at least one polyolefin component, at least one filler component, and optionally an elastomeric  
25           component. The polyolefin component may be any polyolefin which is suitable for film formation such as homo- or co-polymer polypropylene, homo- or co-polymer polyethylenes or blends thereof. A preferred polyolefin is a copolymer of propylene and low density polyethylene, particularly preferred is linear low density polyethylene. The linear low density polyethylene may be a polymer  
30           made from either traditional Ziegler-Natta or metallocene catalysts, or combinations thereof.

In an embodiment of the invention, the films, film composites, and articles made therefrom based on polyolefin filler combinations, when passed through a nip of interdigitating grooved rollers (hereinafter used interchangeably with "ring-rolling") would surprisingly and unexpectedly have improved water vapor transmission rates while maintaining resistance to liquid permeability; and retaining film integrity. Following is a detailed description of certain preferred films, film composites, and/or fabricated disposable articles made therefrom, within the scope of the present invention. Also disclosed are preferred methods of producing these films, film composites, and fabricated disposable articles made therefrom as well as preferred applications thereof. Those skilled in the art will appreciate that numerous modifications to these preferred embodiments can be made without departing from the scope of the invention. For example: though the properties of certain films, film composites, and fabricated articles such as diapers are exemplified, especially after ring-rolling, the films and composites will have numerous other uses. To the extent our description is specific, it is solely for the purpose of illustrating preferred embodiments of our invention and should not be taken as limiting the present invention to these specific embodiments.

It will be appreciated by those of ordinary skill in the art that the films and film composites of certain embodiments of the present invention, can be combined with other polymers or polymer based fabricated articles such as films, fibers, fabrics (including non-woven fabrics) and the like, depending on the intended function of the resulting film, film composite or fabricated article.

As an example of such combinations, by extrusion coating, co-extrusion coating, or by co-extrusion or laminating of the film with other polymer films, e.g. polyolefin, other properties may be achieved. For instance, after ring-rolling an entire film cross-section, certain (machine direction) sections could be extrusion coated to eliminate breathability in those selected portions so coated. Also contemplated are varying combinations of the precursor film, or the film after ring-rolling, with other films, or non-woven fabrics, generally made from one or more polyolefins. Such combinations, while including the precursor or the post ring-rolled film, can include several combinations, such as non-woven/film, film/non-woven, film/non-woven/film, film/film, and the like.

Other methods of improving WVTR of a film or article fabricated from the film, may be used in addition to use of the filled polyolefin and process of passing the filled polyolefin film through the nip of interdigitating grooved rollers described herein, without departing from the intended scope of the invention. For example, including microporous voids through pin-point punctures (also known as "apertured film") to improve the WVTR, in addition to ring-rolling is not excluded by the present invention. Also, it is well known that manipulation of a film by changing quench conditions during melt processing, and/or by irradiating the film will have an effect on WVTR and/or physical properties. Such mechanical or other treatment or manipulation is not excluded by this invention.

Films or film composites employing the polyolefin/filler blends of certain embodiments of the present invention can be oriented, annealed, or crosslinked. Additionally, polyolefin/filler combinations of the present invention can be made into film by processes including blown or cast film manufacturing techniques. The blend components can function to modify barrier, opacity, sealing, cost, or other functions that will be known to those of ordinary skill in the art.

The films or composite structures are often used in infant diapers, toddler training pants, adult incontinence devices, medical drapes and apparel, such as surgical gowns, feminine hygiene articles, and the like. Use of the term "film composites" may include one or more film and/or non-woven layers bonded mechanically, thermally, or adhesively to the film. Such non-woven materials include spun-bond, meltblown, and combinations thereof.

Such non-woven materials are most often made from polyolefins, such as homopolymer polyethylene, copolymer polyethylene (including one or more of  $\alpha$ -olefins of 4-10 carbon atoms, vinyl acetate, ethylenically unsaturated acrylic acid esters, acrylic acid, methacrylic acid, ionomers, polypropylene homopolymers, polypropylene copolymers including one or more of ethylene and  $\alpha$ -olefins of 4-10 carbon atoms, homopolymer and copolymer polypropylene).

Components of A Precursor FilmFilm Forming Polyolefin

Most film forming polyolefins and combinations of film forming  
 5 polyolefins may be used in embodiments of our invention.

Polyolefin Component

The polyolefin component can be any film forming polyolefin, including  
 polyethylene and polypropylene and others, or polyolefin blend. Examples of  
 10 suitable materials are listed in Table 1 below.

**TABLE 1**  
**Suitable Polymers & Relative Benefits**

Polymer	Impact	Tear	Softness	Drawdown
Metallocene Homopolymers and Copolymers (e.g. Exxon Achieve™PD3854)	Preferred	Preferred	Preferred	Most Preferred
Random Copolymer PP (e.g. Exxon PP 9263)	More Preferred	More Preferred	More Preferred	More Preferred
Impact Copolymer polypropylene (e.g. Exxon PP 7623)	Most Preferred	Most Preferred	Most Preferred	Preferred
Homopolymer PP (e.g. Exxon PP 1016)	Preferred	Preferred	Preferred	Preferred
Exxon LD 3003	Preferred	Preferred	Preferred	Preferred
Elastomer	Preferred	Preferred	Preferred	Preferred
Plastomer	Most Preferred	Most Preferred	Most Preferred	Most Preferred

15 Polyethylene

Linear low density polyethylenes are among the materials favored in  
 embodiments of the invention. Linear low density polyethylene (LLDPE),  
 generally that having density from 0.910 to 0.935 g/cm<sup>3</sup> and a melt index from  
 0.01 to 10 dg/min. Another polyolefin that may be considered in such composites  
 20 is very low density polyethylene (VLDPE, also plastomer) which will have  
 densities in the range of from about 0.860 to about 0.910 g/cm<sup>3</sup>.

Conventional high pressure low density polyethylene (LDPE) is another example of a suitable polyethylene which has a density of from 0.910 to 0.925 g/cm<sup>3</sup>.

High density polyethylene (HDPE) having densities in the range of from about 0.935 to about 0.970 g/cm<sup>3</sup> may also be considered. Such polyethylenes may be produced by copolymerizing ethylene with one or more C<sub>4</sub> to C<sub>20</sub>  $\alpha$ -olefin. Generally the preferred  $\alpha$ -olefins include those selected from the group consisting of butene-1, pentene-1, 4-methyl-1-pentene, hexene-1, octene-1, decene-1 and combinations thereof. Most preferred are ethylene copolymers of butene-1, hexene-1, octene-1 and combinations thereof. The comonomers may be present in amounts up to 20 mole percent. The amount of comonomer or comonomers will generally determine density, for instance HDPE will have from 0 to 1 mole percent comonomer, while plastomers with densities lower than 0.900 g/cm<sup>3</sup> will have up to 15 or even 20 mole percent comonomer(s). Such polyethylenes may be made utilizing traditional Ziegler-Natta, chromium based, and metallocene catalysts which may be used with alumoxane and/or ionic activators. Processes useful for preparing such polyethylenes include gas phase, slurry, solution and the like. The density of polyethylenes such as these, in preferred embodiments, will generally be in the range of from about 0.900 and 0.935 g/cm<sup>3</sup>, preferably in the range of from about 0.910 to 0.925 g/cm<sup>3</sup>, most preferably from about 0.915 to 0.920 g/cm<sup>3</sup>. The polyethylenes will have a melt index in the range of from about 0.1 to about 10 g/10 min, preferably 0.5 to 5 g/10 min, generally consistent with film forming conditions.

#### Polypropylene

Polypropylene may be used in conjunction with one or more polyethylenes, or by-itself as the polyolefin component of the precursor film. Polypropylene may be made from many of the catalysts and processes discussed supra, including optional inclusion of one or more  $\alpha$ -olefins. As indicated in Table 1, one of the preferred polymers is a random copolymer having low levels, for example up to about 8 wt.%, of ethylene randomly included in a predominantly polypropylene chain.

### Elastomer

One or more elastomers may be included in the polyolefin component. Such elastomers include, but are not limited to vulcanized natural rubber, ethylene  
5 alpha olefin rubber (EPM), ethylene alpha olefin diene monomer rubber (EPDM), styrene-isoprene-styrene (SIS), styrene-butadiene-styrene (SBS), styrene-ethylene-butylene-styrene (SEBS), ethylene-propylene (EP), ethylene-vinyl acetate copolymer (EVA), ethylene-maleic anhydride (EMA), ethylene-acrylic acid (EEA), butyl rubber and the like. Of these SIS and SBS are preferred, with  
10 SBS more particularly preferred. The range of elastomer inclusion are generally from about 1.4 to about 25 wt.%, preferably from about 1.4 to about 20 wt.%, and more preferably from about 1.4 to 17.2 wt.%.

Amounts of each component can vary with the desired properties for the precursor film or film composite. For instance, a nominal  $0.917 \text{ g/cm}^3$  density  
15 LLDPE may be combined with 4 wt.% of an elastomer. Such a combination might provide improved elastic behavior.

Other components in a film forming polyolefin are not excluded. Such components may include additives such as anti-oxidants, anti-static agents, colors and the like, well known to those of ordinary skill. Further, blending of  
20 polyolefins with polymers is also contemplated. For example, blending of traditional Ziegler Natta catalyzed (ZN), chromium catalyzed (CR), metallocene catalyzed (MCN) and free radical initiated (FR) polyolefins using one or all in a blend as the film forming component is contemplated. For instance including, but not limited to MCN/ZN, MCN/CR, MCN/FR, MCN/ZN/FR, combinations and  
25 the like are contemplated. Other free radical initiated polyethylenes, high pressure polyethylene, ethylene homopolymers as well as ethylene copolymers may be included.

Both in the case of other polyolefins and the elastomeric polymers, the combinations should be generally formable into a film:

30 As used in this application, the term "polyolefin" will mean the polyolefin, any combination of polyolefins, including plastomers, elastomers, additives, and the like.

### Film Physical Property Modification

It was found that the addition of small amounts of low density polyethylene, the polyolefin/filler blend allowed film extrusion at higher throughput levels with some majority polymers but with little to no reduction in film breathability. Low density polyethylene with a Melt Index of 0.9 to 25 (12 MI being preferred), and a density of 0.900 g/cm<sup>3</sup> to 0.930 g/cm<sup>3</sup> may be used.

Further improvements in film impact and tear strength are possible by the addition of plastomers, elastomers, styrenic block co-polymers (SIS, SBS, SEBS), EVA, EMA, EEA, or rubbers. Material grades included are listed in Table 2 below.

TABLE 2

Property Improvement Materials			
Supplier	Grade	Comment 1	Comment 2
Exxon Chemical	Exact™ 3139	7.5 MI	Density=0.900 g/cm <sup>3</sup>
Exxon Chemical	Exact™ 4044	16.5 MI	Density=0.895 g/cm <sup>3</sup>
Exxon Chemical	Exact™ 9095	2.2 MI	Density=0.893 g/cm <sup>3</sup>
Exxon Chemical	Exact™ 3131	3.5 MI	Density=0.900 g/cm <sup>3</sup>
Exxon Chemical	Paxon™ SLX 9106	2.0 MI	Density=0.900 g/cm <sup>3</sup>
Exxon Chemical	Paxon™ SLX 9101	3.5 MI	Density=0.900 g/cm <sup>3</sup>
Dexco	Vector™ 4211	13 MI	
Dexco	Vector™ 4411	40 MI	
Exxon	Vistalon™ 3708	EPDM	
Exxon	Vistalon™ 3030	EPDM	
Shell	Kraton™ G1657	8 MI	SEBS
Union Carbide	UC 9042	5.1 MI	Density=0.900 g/cm <sup>3</sup>
Union Carbide	UC 1085	0.8 MI	Density=0.884 g/cm <sup>3</sup>



### Filler Materials

To impart breathability to polyolefin films, addition of fillers and subsequent straining is known.

To form the precursor film, fillers may be incorporated at relatively high  
5 levels, limited only by the ability of the combination (polyolefin/filler) to be  
formed into a film. The amount of filler added to the polyethylene depends on the  
desired properties of the film including tear strength, WVTR, and stretchability.  
However, it is believed that a film with good WVTR generally cannot be  
produced as is taught herein with an amount of filler less than about 16.5 wt.% of  
10 the polyolefin/filler composition. Further, it is believed that useful films may not  
be made with an amount of the filler in excess of about 71.5 wt.%. While at lower  
than about 16.5 wt.% of filler, the polyolefin/filler composition may not have  
sufficient breathability. Higher amounts of filler may cause difficulty in  
compounding and losses in strength of the final breathable film. Generally, the  
15 range of filler may be in the range of from about 26 to about 67 wt.%, preferably  
in the range of from about 33 to about 60 wt.%. The minimum amount of filler is  
needed to insure the interconnection within the film of voids created at the situs of  
the filler, particularly by the stretching operation to be subsequently performed.  
The preferred filler range is from about 30 to about 70 wt.%, based on the total  
20 weight of the film. More preferred filler loading is from about 40 to about 60  
wt.%.

Fillers useful in certain embodiments of the invention may be any  
inorganic or organic material or combinations thereof having a low affinity for  
and a significantly lower elasticity than the polyolefin component or the optional  
25 elastomeric component. Preferably, the filler should be a rigid material having a  
non-smooth surface, or a material which is treated to render its surface  
hydrophobic. The mean average particle size of the filler is from about 0.5 to  
about 7 microns, preferably from about 1 to about 5, more preferably from about 2  
to about 3.5 microns. It should be understood that smaller particle sizes, such as  
30 from about 0.75 to 2, will provide the best balance of compoundability and  
eventual breathability, but their relative economics makes them generally less  
useful than particle sizes of 3 microns and above. Such particle sizes are preferred

for films having a thickness of from about 0.5-6 mils. Examples of the inorganic fillers include calcium carbonate, talc, clay, kaolin, silica diatomaceous earth, magnesium carbonate, barium carbonate, magnesium sulfate, barium sulfate, calcium sulfate, aluminum hydroxide, zinc oxide, magnesium oxide, calcium oxide, magnesium oxide, titanium oxide, alumina, mica, glass powder, zeolite, silica clay, and combinations thereof, and the like. Calcium carbonate is particularly preferred. The inorganic fillers such as calcium carbonate are preferably surface treated to be hydrophobic so that the filler can repel water to reduce agglomeration of the filler. Also, the surface coating should improve binding of the filler to the polymer while allowing the filler to be pulled away from the polyolefin when the film formed from the polyolefin/filler combination is stretched or oriented. Preferred coatings are stearates, such as calcium stearate, which are generally compliant with FDA regulations. Organic fillers such as wood powder, pulp powder, and other cellulose type powders may be used. Polymer powders such as Teflon<sup>®</sup> powder and Kevlar<sup>®</sup> powder may also be included. Combinations of these fillers are also contemplated.

While a broad range of fillers has been described at a broad range of inclusion parameters based on weight percentages, other embodiments are contemplated. For instance, fillers with much higher or much lower specific gravity may be included in the polyolefin at amounts outside the weight ranges disclosed, they will be understood to be contemplated as embodiments of the invention as long as the final film, after orientation has WVTR or drawn down similar to that described herein. For example, while a preferred filler such as calcium carbonate has a density of  $2.7 \text{ g/cm}^3$ , other examples of suitable fillers include, without limitation, hollow glass beads (density= $0.3 \text{ g/cm}^3$ ), glass fibers or beads (density= $1.11 \text{ g/cm}^3$ ) and barium sulfate (density= $4.6 \text{ g/cm}^3$ ).

#### Compounding of the Polyolefin/Filler Composition

Polyolefin/filler compositions usable in this invention may be compounded in several different ways. The components may be brought into intimate contact by, for example, dry blending these materials and then passing the overall composition through a compounding extruder. Alternatively, the polyolefin and

filler components may be fed directly to a mixing device such as a compounding extruder, higher shear continuous mixer, two roll mill or an internal mixer such as a Banbury mixer. Overall, the objective is to obtain a uniform dispersion of the filler in the polymer without agglomeration, and this is readily achieved by  
5 inducing sufficient shear and heat to cause the polyolefin component to melt. However, time and temperature of mixing should be controlled as is normally done to avoid molecular weight degradation.

#### Film Extrusion and/or Embossing

10 Films contemplated by certain embodiments of the present invention may be made utilizing a polyolefin, by processes including, blown, cast, and cast melt embossed, preferred is a cast melt embossed film process. In such extrusion processes, the films of the present invention can be formed into a single layer film, or may be one layer or more of a multi-layer film or film composite.

15 Alternatively, the polyolefin films described in this disclosure can be formed or utilized in the form of a resin blend where the blend components can function to modify WVTR, physical properties, draw-down, sealing, cost, or other functions. Both blend components and functions provided thereby will be known to those of ordinary skill in the art. Films of the present invention may also be included in  
20 laminated structures. As long as a film, multi-layer film, or laminated structure includes one or more polyolefin/filler film layers having the WVTR, or draw-down, and the like of the film, it will be understood to be contemplated as an embodiment of the present invention.

The film forming composition (polyolefin/polyolefin blends and filler or  
25 fillers) may be manufactured into a precursor film by conventional tubular extrusion (blown bubble process) or by cast extrusion. Film formation by cast extrusion may be more convenient, as the film can be immediately melt embossed as described below.

In the cast extrusion process, the molten resin is extruded from an elongate  
30 die in the form of a web. The web may be pulled over at least one patterned embossing roller to chill and solidify the film with an embossed pattern for reasons discussed further below. The precursor film is may be produced to a

gauge of from about 0.5 to 6 mils, preferably from about 0.75 to about 5 mils, more preferably from about 1 to about 4 mils, most preferably from about 1.5 to about 3 mils, which allows for further stretching as described below. However, those of ordinary skill in the art will understand that many factors affect the response of the precursor film to the ring-rolling process. It is our intent that the film or film part of a film composite will have breathability, and at least a minimum of physical properties to maintain its function, that is the film after ring-rolling (either as part of a composite or by itself) should have the ability to perform its function. For instance in the side panel of a diaper, the film might even have substantial voids, providing excellent breathability, but having enough strength to maintain the physical form of the diaper or other article during its use.

The extrusion temperatures, die temperatures, and embossing roller (if used) temperatures will depend on the composition employed, but generally will be in the following ranges for compositions of the present invention prepared by cast extrusion:

Melt Temperature (°F)	350-550
Die Temperature (°F)	350-550
Embossing Roller Temperature (°F)	50-130

Embossing may be used on the surface of polyolefin films to reduce gloss, although such will not be the films primary function in a ring-rolling process. Embossing can be imposed on the precursor film surface at the time of the film fabrication for cast extrusion, or at a subsequent time for cast or tubular extrusion by procedures well known in the art.

For the present invention, embossing may impose a pattern of different film thicknesses within the precursor film, and can be conducted with an micro/macro pattern, e.g. cross-hatching, dots, lines, circles, diamonds, hexagons, etc. The pattern can be either in line and/or off line and the rollers can be engraved with either pin up and/or pin down type configurations.

30

40

50

### Use of the Precursor Film

Traditionally, breathable film has been made using such film precursors as described above, and then orienting the film by a variety of techniques, such as tentering in one or both of the machine direction (MD) or cross or transverse direction (TD). The oriented and breathable film could then be used for a variety of end use articles, such as diapers (usually back sheets, but also top sheets), feminine hygiene items, bandages, catamenial pads, panty liners, incontinent briefs, and the like. However, use of certain embodiments of the present invention will include the precursor film either by itself or a film composite in an interdigitating grooved roller process. By film composite, we intend that one or more additional layers or materials are added or laminated to the film. Such additional materials and layers include synthetic woven, synthetic non-woven, synthetic knit, non-woven, apertured film, macroscopically expanded three-dimensional formed film, filled compositions or laminates and/or a combination of these items. The non-wovens may be made by processes including, but not limited to spunlace, spunbond, meltblown, carded and or air-through or calendar bonded. The materials or layers of the composite can be combined by many method known to those of ordinary skill. For instance, adhesives (including spray adhesives, hot melt adhesives, latex based adhesives and the like), thermal bonding, ultra-sonic bonding, extrusion lamination, needle punching, and the like. For instance, in the manufacture of infant diapers, toddler training pants, adult incontinence devices, feminine hygiene items, medical gowns, medical drapes, and house wrap, parts or all of the final product may be assembled (by for instance heat or adhesive lamination) then the partial or finished construction is passed through one or more pairs of interdigitating grooved rollers to render the precursor film high in WVTR.

### Stretching

High WVTR film, film composites or fabricated articles made therefrom may achieved by stretching the precursor film to form interconnected voids prior to ring-rolling. Stretching or "orientation" of the film may be carried out monoaxially in the machine direction (MD) or the transverse direction (TD) or in

both directions (biaxially) either simultaneously or sequentially using conventional equipment and processes following cooling of the precursor film.

Blown films are preferably stretched in the machine direction or in both directions whereas cast films are preferably stretched in the transverse direction.

5 For orientation in the MD, the precursor film is passed around two rollers driven at different surface speeds and finally to a take up roller. The second driven roller which is closest to the take up roller is driven faster than the first driven roller. As a consequence the film is stretched between the driven rollers.

10 Stretching of melt embossed precursor films either using both a tentering device and a directly in a ring-rolling device or just the ring-rolling device produces breathable films having the desired water vapor permeability. The resulting films had greater permeability in the areas of reduced thickness in comparison to the areas of greater thickness.

15 Preferably, the film is stretched through a pair or pairs of interdigitating rollers. In this embodiment machine direction orientation is accomplished by stretching the film through a gear like pair of rollers. Transverse direction orientation is accomplished by stretching the film through a pair of disk like rollers. The preferred embodiment employs rollers with a tooth pitch,  $W=0.080$ ", however a pitch of  $0.040$ " to  $0.500$ " is acceptable. The tooth depth (d), is 20 preferably  $0.100$ ", however a depth of  $0.030$ " to  $0.500$ " is acceptable (see Fig. 4). For the transverse direction orientation rollers, the depth may be up to  $1$ " as mechanical interference is less of an issue with the TD rollers. The preferred embodiment employs interdigitating grooved rollers that can be temperature controlled from  $50^{\circ}\text{F}$  to  $210^{\circ}\text{F}$ , more preferred is a range of from  $70^{\circ}\text{F}$ - $190^{\circ}\text{F}$ , 25 more preferred is  $85^{\circ}\text{F}$ - $180^{\circ}\text{F}$ , most preferred is  $95^{\circ}\text{F}$ - $159^{\circ}\text{F}$ . Roller temperature may be maintained through internal liquid, electrical systems, an external source of cooling/heating, combinations thereof, and other methods which will be apparent to those of ordinary skill in the art. The preferred embodiment is internal liquid cooled/heated rollers.

30 The depth of engagement of the roller teeth determines the amount of orientation imparted on the film. A balance must be drawn between the depth of

engagement and the level of filler in the film, as many properties are affected as depicted in Table 3 below.

**TABLE 3**  
**Relationships Between Process Factors**  
**and Resulting Film Properties**

Increasing Process Factor	WVTR	Dart Impact	Basis Weight	CD Tensile	MD Tear
CaCO <sub>3</sub>	Increase	Decrease			Decrease
MD Orientation	Increase	Decrease	Decrease		Decrease
TD Orientation	Increase	Decrease	Decrease	Decrease	
Roll Temperature	Increase		Decrease		

Although not thoroughly investigated, controlling of the strain on the film during stretching is believed to be important to controlling the WVTR. For stretching in the transverse direction, strain is controlled for a given stretch ratio by adjusting the film speed and the stretching distance. The stretching distance is measured, between the point where the film starts to increase in width to the closest point where the film is fully stretched. For stretching in the machine direction, strain is controlled for a given stretch ratio by controlling film speed and the gap between the first and second driven rollers.

A range of stretching ratios from 1:2 to 1:5 prove satisfactory for MD stretching with a ratio of 1:4 being preferred. A range of stretching ratios of 1:2 to 1:5 prove satisfactory for TD stretching with a ratio of 1:4 being preferred.

It is a further object of this invention to provide such a process for producing a barrier layer having high liquid strikethrough resistance.

The process of ring-rolling also may activate the elasticity of the web (dependent upon specific ring-rolling pattern used), in addition to imparting breathability to the web.

Precursor webs containing elastomeric components add to the elasticity developed during the ring-rolling process.

### Ring-Rolling Process

To illustrate the process, the term web or webs are used. As used herein, the term web will include a precursor film and optionally one or more additional webs or layers, as discussed above, for instance one or more non-woven webs and/or one or more film webs. Such web components can be pre-assembled or laminated. Prior to ring-rolling, at least one additional web may be added. Web 10 and alternatively optional web 11 may be webs of a precursor film with either another film or fabric (11) the precursor film will have a thickness from 0.5 to 6 mils. For example, the optional web 11 may be melt-blown webs of the type taught in the article entitled "Superfine Thermoplastic Fibers" by Van A. Wentz, appearing in *Industrial Engineering Chemistry*, August, 1956, Vol. 48, No. 8 (pages 1342-1346). While melt-blown material may be nylon, polyester, or any polymer or polymer blend capable of being melt-blown, a melt-blown polypropylene web is preferred. A melt-blown web could comprise two or more zones of different melt-blown polymers. Melt-blown webs having a basis weight of up to about 30 g/m<sup>2</sup> or greater can be used in the present invention, but lower weight webs are generally preferred in order to minimize the cost of the barrier layer produced therefrom. Technology provides for the production of melt-blown webs with a minimum basis weight of about 3 g/m<sup>2</sup>, but available commercial melt-blown webs generally have a basis weight of 10 g/m<sup>2</sup> or more. The preferred basis weight for optional web 11 is from about 10 g/m<sup>2</sup> to about 30 g/m<sup>2</sup>; most preferably from about 10 g/m<sup>2</sup> to about 20 g/m<sup>2</sup>. The density of melt-blown optional web 11 is preferably up to about 0.15 g/cm<sup>3</sup> and most preferably up to about 0.1 g/cm<sup>3</sup>. Web 10 and optional web 11 may be the same or different.

Web 10 and (when present) optional web 11 have preferably been rolled up together as plies with adjacent surfaces on feed roller 20. They are unrolled from feed roller 20 retaining their contiguous relationship and passed into the nip of interdigitating grooved rollers 24 and 25. Grooved rollers 24 and 25 have grooves perpendicular to the axis of the rollers (parallel to the machine direction) as shown in Fig. 2 which is a sectional view of grooved rollers 24 and 25 taken along line 2-2 of Fig. 1.



It has been found that the web 10 and optional web 11 will be stretched more uniformly with less tendency to tear the webs when interdigitating grooved rollers 24 and 25 are heated. The rollers are preferably heated such that their surface temperature are within the range of about 160°F to 220°F; more preferably within the range of 180°F to 200°F.

Fig. 1 shows a preferred arrangement of interdigitating grooved rollers 24 and 25 being located with their centers in a horizontal plane and webs 10 and 11 contacting the surface of roll 24 for about one-fourth of a revolution before entering the nip between rollers 24 and 25; this provides an opportunity for the web or webs 10 and optional web 11 to be heated prior to entering the nip. However, interdigitating grooved rollers 24 and 25 could be positioned with their centers in a vertical plan or at any other angle and web 10 and optional web 11 could be fed directly into the nip of the rollers. Preheating of webs 10 and 11 if found to be necessary in order to avoid tearing of the webs, could be accomplished in any conventional manner. Fig. 4 illustrates how the web 10 is stretched between the interdigitating grooved rollers 24 and 25.

The webs where two or more webs are fed is stretched and enmeshed while passing between the interdigitating grooved rollers 24 and 25 and are thus lightly bonded together producing final product 12. Where final improved WVTR composite film 12 has been stretched in the cross-machine direction by the grooved rollers 24 and 25 of Figs. 1 and 2, a device such as a curved Mount Hope roll 26 or tenter clamps is needed to extend the now high WVTR film or film composite to its fullest width. The extended and smoothed film 12 is then rolled up on a takeup roller 27.

The amount of lateral stretch imparted to web plies by the grooved rollers 24 and 25 will depend on the shape and depth of the grooves of the rollers, and on the gap spacing between the rollers.

U.S. Patent No. 4,223,059, issued to Eckhard C.A. Schwarz on Sept. 16, 1980 discloses interdigitating rollers having grooves of generally sine-wave shape cross-section which may be used for the present invention. U.S. Patent No. 4,153,664 issued to Rinehardt N. Sabee on May 8, 1979, discloses the stretching of polymeric webs by ring-rolling with rollers having grooves with a variety of

shapes. The shape of the grooves of the rollers will generally determine whether the web is stretched uniformly or at incremental, spaced portions of the web. Incremental stretching of the web is more likely to cause some local tearing of film or film composites which would damage the liquid strikethrough resistance of the film and, therefore, is not preferred for the present invention.

A preferred groove pattern for interdigitating rollers 24 and 25 is shown in Fig. 3 which is an enlarged view of area 3 of Fig. 2. Fig. 3 shows a partial cutaway view of interdigitating rollers 24 and 25. Teeth 54 and 55 of grooved roller 24 intermesh with teeth 51, 52 and 53 of grooved roller 25. The length of the teeth is 3.81 mm, and the distance 61 between the centerlines of adjacent teeth on each roller is 2.54 mm. The teeth have generally straight sides which are at an angle 62 from a plane perpendicular to the axis of rollers 24 and 25 of 9° 17". The land at the base of the teeth has a radius 63 of 0.51 mm. Sharp corners 66 at the ends of the teeth are removed.

It is preferred that the interdigitating grooves of rollers 24 and 25 be perpendicular to the axis of the rollers. In this way, the maximum number of grooves of a given size will engage the web 10 and 11 at the same time and impact stretch to the webs. By having the maximum number of teeth engage the web at a given time, a more uniform stretching of the webs is achieved so that local tearing of the film or film composite is minimized. The stretched film 12 can be easily smoothed in the cross-machine direction.

A reproducible gap setting between grooved rollers 24 and 25 can be achieved by having the bearing of one of the grooved rollers, e.g. 24, stationary while those of the other grooved roller 25 can be moved in the horizontal direction. Grooved roller 25 is moved in the horizontal direction. Grooved roller 25 is moved toward roll 24 until its teeth are intermeshed with those of grooved roller 24 and it will move no further. The bearings of grooved roller 25 are then moved away from grooved roller 24 a measured distance, the gap setting. The preferred gap setting for practicing the present invention are from about 0.76 mm. to about 1.65 mm. With grooved rollers 24 and 25 having a tooth configuration as shown in Fig. 3 and described above, the maximum width of film or film composite layer 12 which can be achieved for a single pass is about 2½ to 3 times

the width of starting webs 10 and 11. By incising the gap between grooved rollers 24 and 25, the amount of lateral stretch imparted to webs 10 and 11 is decreased. Therefore, the width of film or film composite 12 compared to the width of starting web can be varied for a single pass between grooved rollers 24 and 25 from a maximum increase of  $2\frac{1}{2}$  to 3 times to no increase by the appropriate gap setting.

If it is desired to stretch the web more than can be achieved by a single pass between the grooved rollers, multiple passes between grooved rollers 24 and 25 can be used.

10 Basis weight is generally an important property desired to be controlled for film or film composite layer (total ring-rolled web) 12. For cost reasons, the lightest film or film composite that will provide sufficient breathability is desired. A basis weight of the film produced by itself will be generally above  $20 \text{ g/cm}^2$ . The desired basis weight can be obtained by controlling the amount of stretch  
15 imparted to web 10 and optional web 11 by grooved rollers 24 and 25 as described above, and by the selection of the basis weights of the starting webs 10 and 11. For the present invention, starting webs 10 and 11 have a cumulative basis weight in the range of about 1.1 to 4 times the ultimate desired basis weight, preferably in the range of about 1.5 to 3 times the desired basis weight, most preferably about 2  
20 times the desired basis weight. Correspondingly, the desired width of breathable film or film composite 12 can be achieved by selecting a proper combination of stretch imparted by the grooved rollers 24 and 25 and initial width of starting webs 10 and 11. For the present invention, the initial width of starting webs 10 and 11 before passing between grooved rollers 24 and 25 is within the range of about 0.9 to about 0.25 times the desired width, preferably within the range of  
25 about 0.7 to about 0.3 times the desired width, most preferably about 0.5 times the desired width.

#### Properties of films produced

##### 30 WVTR

In an embodiment of the present invention, certain films and articles made therefrom have higher WVTR than previously thought possible. The WVTR of

such films are greater than  $100 \text{ g/m}^2/24 \text{ hr}$  @  $37.8^\circ\text{C}$ , 100% RH, preferably greater than 1000, and more preferably greater than  $2000 \text{ g/m}^2/24 \text{ hr}$  @  $37.8^\circ\text{C}$ , 100% RH. Some applications benefit from film with a WVTR at or greater than  $10,000 \text{ g/m}^2/24 \text{ hr}$  @  $37.8^\circ\text{C}$ , 100% RH.

5

#### Test Procedures

The test procedures used to determine the unique properties of the layers of the present invention and to provide the test results in the examples below are as follows:

10

#### Water Vapor Transmission Rate (WVTR)

Both a Mocon W1, and a Mocon W600 instrument are used to measure water evaporated from a sealed wet cell at  $37.8^\circ\text{C}$  through the test film and into a stream of dry air or nitrogen. It is assumed that the relative humidity on the wet side of the film is approximately 100%, and the dry side is approximately 0%.  
The amount of water vapor in the air stream is precisely measured by a pulse modulated infra red (PMIR) cell. Following appropriate purging of residual air, and after reaching a steady state water vapor transmission rate, a reading is taken. WVTR of the test films are reported as grams of water/meter<sup>2</sup>/day. The output of the unit is calibrated to the results obtained with a film of known WVTR. The testing protocols are based on ASTM F1249-90.

20

#### Mocon W1

25

The Mocon W1 has a single test cell and an analog chart recorder. Air is pumped through a desiccant dryer, then through the test cell, and then past the PMIR sensor. A 5 minute purge of residual air is followed by a 6 minute test cycle with controlled air flow. The result is a steady state value for WVTR. The purge and test cycles are controlled manually. The unit is calibrated to a film with a known WVTR every 12 hours. Calibration results are control charted and adjustments are made to the instrument calibration accordingly.

30

Mocon W600

The Mocon W600 has 6 measurement cells with PMIR data fed into a computer. Nitrogen is fed through a desiccant dryer, then through the active test cell, then past the PMIR sensor. In addition to data compilation, the computer controls test cycle sequencing. All cells are purged simultaneously for an 8 minute period. This is followed by an 8 minute test cycle for each of the six cells. Total testing time is 56 minutes. Two of the test cells always measure reference films with a known WVTR.

10 Gurley Porosity

Teledyne Gurley Model 4190 Porosity Tester with sensitivity attachment is used. The procedure is as follows:

- a) Cut a strip of film (~2" wide) across the entire web width,
  - 15 b) Insert a film sample to be tested between orifice plates,
  - c) Set the sensitivity adjustment on "5",
  - d) Turn the inner cylinder so that the timer eye is vertically centered below the 10 cm<sup>3</sup> silver step on the cylinder,
  - e) Reset the timer to zero,
  - 20 f) Pull the spring clear of the top flange and releasing the cylinder,
- When the timer stops counting, the test is completed. The number of counts is multiplied by 10 and the resulting number is "Gurley seconds per 100 cm<sup>3</sup>".

25 It will be appreciated by those of ordinary skill in the art that the films of m-polyethylene resins of certain embodiments of the present invention, can be combined with other materials, depending on the intended function of the resulting film.

30 Other methods of improving and/or controlling WVTR properties of the film or container may be used in addition to the methods described herein without departing from the intended scope of the invention. For example, mechanical treatment such as micro pores.

### Liquid Column Strikethrough Resistance Test

The liquid strikethrough resistance test is a method for determining the water pressure in millimeters of water at which water penetrates a repellent barrier layer at a specified fill rate and with the water and barrier layer at a specified temperature. Such a test is described in *INDA Journal*, Vol. 5, No. 2, Karen K. Leonas; the strikethrough resistance of embodiments of the invention are from 50 - 500 cm.

The following non-limiting examples are provided for illustrative purposes only.

## EXAMPLES

### Examples 1-12

LLDPE/CaCO<sub>3</sub> films are made utilizing the following conditions, materials and equipment shown in Table 4.

Examples 1-12 used LL-3003.09 (a 3 MI, 0.917 g/cm<sup>3</sup> polyethylene (Z-N) available from Exxon Chemical Co., Houston, TX.) containing levels of CaCO<sub>3</sub> as shown in Table 4, blended with 100 parts of LL-3003.

### Examples 13-16

Example 13-16 were made under the conditions shown in Table 4, Examples 1-12, but with Exceed<sup>®</sup> ECD-112 (a 3.4 MI, 0.917 g/cm<sup>3</sup> density m-LLDPE from Exxon Chemical Co., Houston, TX) with filler, master batch (MB) and elastomer levels as shown in Table 5.

Examples 1-4, 9, 10, 11, 12, 13, 14 and 15 were run on a Davis Standard cast line. Examples 9, 10, 11, 12, 14, and 15 were oriented in the TD, Example 9, 10, 11, 12, and 15 were further MD drawn. Examples 5, 6, 7, 8, and 16 were run on a blown film extruder.

Each film sample was run through various ring-rolling apparatus as shown in Tables 5, 6 and 7, with the results for basis weight shown in Table 5, the results for WVTR in Table 6, the results for air porosity shown in Table 7.

TABLE 4

Condition	Example 1	Example 2	Example 3	Example 4	Example 5	Example 6	Example 7	Example 8
Material	A	B	B	B	C	D	E	F
Process	Cast/TD	Cast	Cast	Cast	Blown	Blown	Blown	Blown
Ext. RPM	17	6	8	11	45	65	65	61
Screen PSI	2600	2150	2380	2800	5290	6000	5730	6300
Die PSI	940	750	810	900	N/A	N/A	N/A	N/A
Melt Temp	390	374	378	388	400	410	411	430
Up Width	23	28	28	28	9	11	11	11
Down Width	62.4	N/A	N/A	N/A	N/A	N/A	N/A	N/A
FPM	165	65	77	102	30	28	30	28
MD Drawn	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

Condition	Example 9	Example 10	Example 11	Example 12	Example 13	Example 14	Example 15	Example 16
Material	G	B	H	B	B	B	B	E
Process	Cast/TD/ MD/Drawn	Cast/TD/ MD Drawn	Cast/TD/ MD Drawn	Cast/TD/ MD Drawn	Cast	Cast/TD	Cast/TD/ MD Drawn	Blown
Ext. RPM	15	21	15	22	19	19	19	35
Screen PSI	3600	3440	3138	3302	3740	3740	3740	4750
Die PSI	N/A	N/A	N/A	N/A	1270	1270	1270	N/A
Melt Temp	414	402	390	350	430	430	430	425
Up Width	21	21	21	24	22	22	22	10
Down Width	83	77	82	89	N/A	63	63	N/A
FPM	181	195	186	140	340	340	340	25
MD Drawn	1:3	1:3	1:3	1:3	N/A	N/A	1:3	N/A

TABLE 4 (continued)

	<u>CaCO<sub>3</sub></u>	<u>EVA</u>	<u>SBS</u>
A	37%		
B	50%		
C	40%	8%	12%
D	35%	12%	18%
E	30%	16%	24%
F	40%	20%	
G	45%		
H	47%		

<u>Material</u>	<u>LLDPE</u>
A	63%
B	50%
C	40%
D	35%
E	30%
F	40%
G	55%
H	53%



TABLE 5  
BASIS WEIGHT (Grams/Square Meter)

PROPERTIES BEFORE ACTIVATION					PROPERTIES AFTER ACTIVATION					
Example	Mat. Comp.**	Mfg. Meth.*	Weight g/m <sup>2</sup>	WVTR	Air Porosity scc/100cm <sup>3</sup>	Type 1 Manual Stretch	Type 2 Ring-Roll 0.400 DOE	Type 3 Ring-Roll 0.175 DOE	Type 4 Ring-Roll 0.100 DOE	Type 5 Tooth Pattern
1	A	AA	22	1318	>10000		Destroyed	Destroyed	21	N/A
2	B	BB	79	<100	N/A		23	N/A	N/A	N/A
3	B	BB	86	<100	N/A		25	N/A	N/A	N/A
4	B	BB	108	<100	N/A		29	N/A	N/A	N/A
5	C	CC	53	<100	N/A			N/A	N/A	
6	D	CC		<100	N/A			N/A	N/A	
7	E	CC	49	<100	N/A		21	N/A	N/A	
8	F	CC	54	<100	N/A			N/A	N/A	N/A
9	G	DD	18	8000	190		Destroyed		N/A	N/A
10	B	DD	25	7000	300		Destroyed		N/A	N/A
11	H	DD	20	6100	642		Destroyed		N/A	N/A
12	B	DD	36	7100	898		Destroyed		N/A	N/A
13	B	BB	73	<100	N/A	29				
14	B	AA	23	7900	210					
15	B	DD	21	8000	263	22				
16	B	CC	22	<100	N/A	11				

\*\*\*Manufacturing Methods

\*\*Manufacturing Methods

AA CAST/TD

BB CAST

CC BLOWN

DD CAST/TD/MD DRAWN

\*Compositions of Raw Materials

LLDPE

CaCO<sub>3</sub>

EVA

SBS

A 63%

B 50%

C 40%

D 35%

E 30%

F 40%

G 55%

H 53%

8%

12%

12%

16%

20%

8%

12%

18%

24%

20%

**TABLE 6**  
**WATER VAPOR TRANSMISSION RATE (g/square meter/24 hours)**

PROPERTIES BEFORE ACTIVATION						PROPERTIES AFTER ACTIVATION				
Example	Mat. Comp.**	Mfg. Meth.*	Wweight g/m <sup>2</sup>	WVTR	Air Porosity sec/100cm <sup>3</sup>	Type 1 Manual Stretch	Type 2 Ring-Roll 0.400 DOE	Type 3 Ring-Roll 0.175 DOE	Type 4 Ring-Roll 0.100 DOE	Type 5 Tooth Pattern
1	A	AA	22	1318	>10000		Destroyed	Destroyed	750	N/A
2	B	BB	79	<100	N/A		1300	N/A	N/A	N/A
3	B	BB	86	<100	N/A		1300	N/A	N/A	N/A
4	B	BB	108	<100	N/A	1600	1100	N/A	N/A	N/A
5	C	CC	53	<100	N/A	400	360	N/A	N/A	800
6	D	CC		<100	N/A	200	350	N/A	N/A	400
7	E	CC	49	<100	N/A	200	290	N/A	N/A	200
8	F	CC	54	<100	N/A	200	240	N/A	N/A	450
9	G	DD	18	8000	190		Destroyed	7100	N/A	N/A
10	B	DD	25	7000	300		Destroyed	9200	N/A	N/A
11	H	DD	20	6100	642		Destroyed	9000	N/A	N/A
12	B	DD	36	7100	898	6900	Destroyed	7850	N/A	N/A
13	B	BB	73	<100	N/A	1400				
14	B	AA	23	7900	210	6400				
15	B	DD	21	8000	263	7350				
16	B	CC	22	<100	N/A	2600				

\*\*Manufacturing Methods

AA CAST/TD  
BB CAST  
CC BLOWN  
DD CAST/TD/MD DRAWN

\*Compositions of Raw Materials

	LLDPE	CaCO <sub>3</sub>	EVA	SBS
A	63%	37%		
B	50%	50%		
C	40%	40%	8%	12%
D	35%	35%	12%	18%
E	30%	30%	16%	24%
F	40%	40%	20%	
G	55%	45%		
H	53%	47%		

**TABLE 7**  
**AIR POROSITY (Seconds/100cm<sup>3</sup>/Square inch)**

AIR POROSITY (Seconds/100cm <sup>3</sup> /Square cm)										
PROPERTIES BEFORE ACTIVATION					PROPERTIES AFTER ACTIVATION					
Example	Mat. Comp.**	Mfg. Meth.*	Weight g/m <sup>2</sup>	WVTR	Air Porosity sec/100cm <sup>3</sup>	Type 1 Manual Stretch	Type 2 Ring-Roll 0.400 DOE	Type 3 Ring-Roll 0.175 DOE	Type 4 Ring-Roll 0.100 DOE	Type 5 Tooth Pattern
1	A	AA	22	1318	>10000		Destroyed	Destroyed	>10000	N/A
2	B	BB	79	<100	N/A		4165	N/A	N/A	N/A
3	B	BB	86	<100	N/A		9966	N/A	N/A	N/A
4	B	BB	108	<100	N/A		5685	N/A	N/A	N/A
5	C	CC	53	<100	N/A		>10000	N/A	N/A	890
6	D	CC		<100	N/A		>10000	N/A	N/A	6320
7	E	CC	49	<100	N/A		>10000	N/A	N/A	>10000
8	F	CC	54	<100	N/A		>10000	N/A	N/A	640
9	G	DD	18	8000	190		Destroyed	33	N/A	N/A
10	B	DD	25	7000	300		Destroyed	48	N/A	N/A
11	H	DD	20	6100	642		Destroyed	5	N/A	N/A
12	B	DD	36	7100	898		Destroyed	17	N/A	N/A
13	B	BB	73	<100	N/A					
14	B	AA	23	7900	210					
15	B	DD	21	8000	263	258				
16	B	CC	22	<100	N/A					
**Manufacturing Methods										

### \*\*\*Manufacturing Methods

AA CAST/TD

BB CAST

CC BLOWN

DD CAST/TD/MD DRAWN

### \*Compositions of Raw Materials

## POSITIONS

$$\underline{\text{CaCO}_3}$$

EVA      SBS

37%

1

3

**CASI  
DI OVINI**

**F**

•

B. 50%

50% 50%

50% 50%

Year	50%	50%
1971	50%	50%
1972	50%	50%
1973	50%	50%
1974	50%	50%
1975	50%	50%
1976	50%	50%
1977	50%	50%
1978	50%	50%
1979	50%	50%
1980	50%	50%
1981	50%	50%
1982	50%	50%
1983	50%	50%
1984	50%	50%
1985	50%	50%
1986	50%	50%
1987	50%	50%
1988	50%	50%
1989	50%	50%
1990	50%	50%
1991	50%	50%
1992	50%	50%
1993	50%	50%
1994	50%	50%
1995	50%	50%
1996	50%	50%
1997	50%	50%
1998	50%	50%
1999	50%	50%
2000	50%	50%
2001	50%	50%
2002	50%	50%
2003	50%	50%
2004	50%	50%
2005	50%	50%
2006	50%	50%
2007	50%	50%
2008	50%	50%
2009	50%	50%
2010	50%	50%
2011	50%	50%
2012	50%	50%
2013	50%	50%
2014	50%	50%
2015	50%	50%
2016	50%	50%
2017	50%	50%
2018	50%	50%
2019	50%	50%
2020	50%	50%
2021	50%	50%
2022	50%	50%
2023	50%	50%
2024	50%	50%
2025	50%	50%
2026	50%	50%
2027	50%	50%
2028	50%	50%
2029	50%	50%
2030	50%	50%
2031	50%	50%
2032	50%	50%
2033	50%	50%
2034	50%	50%
2035	50%	50%
2036	50%	50%
2037	50%	50%
2038	50%	50%
2039	50%	50%
2040	50%	50%
2041	50%	50%
2042	50%	50%
2043	50%	50%
2044	50%	50%
2045	50%	50%
2046	50%	50%
2047	50%	50%
2048	50%	50%
2049	50%	50%
2050	50%	50%
2051	50%	50%
2052	50%	50%
2053	50%	50%
2054	50%	50%
2055	50%	50%
2056	50%	50%
2057	50%	50%
2058	50%	50%
2059	50%	50%
2060	50%	50%
2061	50%	50%
2062	50%	50%
2063	50%	50%
2064	50%	50%
2065	50%	50%
2066	50%	50%
2067	50%	50%
2068	50%	50%
2069	50%	50%
2070	50%	50%
2071	50%	50%
2072	50%	50%
2073	50%	50%
2074	50%	50%
2075	50%	50%
2076	50%	50%
2077	50%	50%
2078	50%	50%
2079	50%	50%
2080	50%	50%
2081	50%	50%
2082	50%	50%
2083	50%	50%
2084	50%	50%
2085	50%	50%
2086	50%	50%
2087	50%	50%
2088	50%	50%
2089	50%	50%
2090	50%	50%
2091	50%	50%
2092	50%	50%
2093	50%	5

50%

Year	50%	50%
1970	100%	100%
1971	100%	100%
1972	100%	100%
1973	100%	100%
1974	100%	100%
1975	100%	100%
1976	100%	100%
1977	100%	100%
1978	100%	100%
1979	100%	100%
1980	100%	100%
1981	100%	100%
1982	100%	100%
1983	100%	100%
1984	100%	100%
1985	100%	100%
1986	100%	100%
1987	100%	100%
1988	100%	100%
1989	100%	100%
1990	100%	100%
1991	100%	100%
1992	100%	100%
1993	100%	100%
1994	100%	100%
1995	100%	100%
1996	100%	100%
1997	100%	100%
1998	100%	100%
1999	100%	100%
2000	100%	100%
2001	100%	100%
2002	100%	100%
2003	100%	100%
2004	100%	100%
2005	100%	100%
2006	100%	100%
2007	100%	100%
2008	100%	100%
2009	100%	100%
2010	100%	100%
2011	100%	100%
2012	100%	100%
2013	100%	100%
2014	100%	100%
2015	100%	100%
2016	100%	100%
2017	100%	100%
2018	100%	100%
2019	100%	100%
2020	100%	100%
2021	100%	100%
2022	100%	100%
2023	100%	100%
2024	100%	100%
2025	100%	100%
2026	100%	100%
2027	100%	100%
2028	100%	100%
2029	100%	100%
2030	100%	100%
2031	100%	100%
2032	100%	100%
2033	100%	100%
2034	100%	100%
2035	100%	100%
2036	100%	100%
2037	100%	100%
2038	100%	100%
2039	100%	100%
2040	100%	100%
2041	100%	100%
2042	100%	100%
2043	100%	100%
2044	100%	100%
2045	100%	100%
2046	100%	100%
2047	100%	100%
2048	100%	100%
2049	100%	100%
2050	100%	100%
2051	100%	100%
2052	100%	100%
2053	100%	100%
2054	100%	100%
2055	100%	100%
2056	100%	100%
2057	100%	100%
2058	100%	100%
2059	100%	100%
2060	100%	100%
2061	100%	100%
2062	100%	100%
2063	100%	100%
2064	100%	100%
2065	100%	100%
2066	100%	100%
2067	100%	100%
2068	100%	100%
2069	100%	100%
2070	100%	100%
2071	100%	100%
2072	100%	100%
2073	100%	100%
2074	100%	100%
2075	100%	100%
2076	100%	100%
2077	100%	100%
2078	100%	100%
2079	100%	100%
2080	100%	100%
2081	100%	100%
2082	100%	100%
2083	100%	100%
2084	100%	100%
2085	100%	1

A	50%	BLOWN
B	50%	CAST/TDMD
C	50%	CAST/TDMD

Example 17

A blend of 57% ECC FilmLink 400  $\text{CaCO}_3$  was combined with 33% Exxon PD 7623 Impact Copolymer, 2% Exxon LD-200.48, and 8% Exxon Exact 3131 oriented in interdigitating rollers of 0.080" pitch. The MD depth of engagement was 0.020", and the TD depth of engagement was 0.040". The temperature of the interdigitating grooved rollers was 140°F.

Example 18

A blend of 57% ECC FilmLink 400  $\text{CaCO}_3$  was combined with 33% Exxon PD 7623 Impact Copolymer, 2% Exxon LD-200.48, and 8% Exxon Exact 3131 oriented in interdigitating rollers of 0.080" pitch. The MD depth of engagement was 0.020", and the TD depth of engagement was 0.040". The temperature of the interdigitating grooved rollers was 110°F.

Example 19

A blend of 57% ECC FilmLink 400  $\text{CaCO}_3$  was combined with 33% Exxon PD 7623 Impact Copolymer, 2% Exxon LD-200.48, and 8% Exxon Exact 3131 oriented in interdigitating rollers of 0.080" pitch. The MD depth of engagement was 0.020", and the TD depth of engagement was 0.040". The temperature of the interdigitating grooved rollers was 70°F.

As can be seen from Table 8, the WVTR rise from a roller temperature of 70°F (considered ambient temperature) to 110°F then 140°F is dramatic, unexpected and surprising. It would be expected that heating the film would soften it and the polymer would not tear away from the filler as easily. Such a result would likely cause fewer or smaller pores, and thereby reduced WVTR. Accordingly, the significant increase in WVTR produced by using heated rollers is both surprising and unexpected.

TABLE 8

	Example 17	Example 18	Example 19
Roller Temperature (°F)	140	110	70
Basis Weight (g/m <sup>2</sup> )	43	40	39
WVTR (g/m <sup>2</sup> /day)	4100	3000	1900
Dart Impact (g)	240	300	300
MD Ultimate (g/in)	1585	1532	1453
MD Elongation (%)	408	431	442
TD @ 5% (g/in)	457	389	388
TD Ultimate (g/in)	785	1166	1049
TD Elongation (%)	351	358	357
MD Elmendorf Tear (g)	166	208	205

A linear regression analysis reveals that with the above fixed formulation, depth of activation water vapor transmission rate is predicted by the following equation:

$$\text{WVTR} = -329.73 + 31.2162 * \text{Roller Temperature (°F)}$$

#### Example 20

A blend of 52% ECC FilmLink 400 CaCO<sub>3</sub> was combined with 48% Exxon PD 7623 Impact Copolymer Polypropylene. Film was oriented off line with interdigitating rolls of 0.100" pitch. The MD depth of engagement was 0.030" and the TD depth of engagement was 0.019".

#### Example 21

A blend of 52% ECC FilmLink 400 CaCO<sub>3</sub> was combined with 40% Exxon PD 7623 Impact Copolymer, 2% Exxon LD-202.48, and 6% Exxon SLX9101. Film was oriented in interdigitating rolls of 0.080" pitch. The MD depth of engagement was 0.028", and the TD depth of engagement was 0.034".

#### Example 22

A blend of 55% ECC FilmLink 400 CaCO<sub>3</sub> was combined with 31% Exxon PD 7623 Impact Copolymer, 4% Exxon LD-202.48, 2% Ampacet 110131

TiO<sub>2</sub> concentrate, and 8% Exxon Exact 3131. Film was oriented in interdigitating rolls of 0.080" pitch. The MD depth of engagement was 0.021", and the TD depth of engagement was 0.037".

5 Table 9 demonstrates the high absolute values of tear and impact strength relative to known polypropylene breathable films. Also shown is the further property improvement made by the addition of minority amounts of other polyolefins.

TABLE 9

Film Properties

10

	Example 20	Example 21	Example 22
Basis Weight (g/m <sup>2</sup> )	41.0	40.6	40.3
WVTR (g/m <sup>2</sup> /day)	1457	1462	1400
Dart Impact (g)	210	315	315
MD Ultimate (g/cm)	625	609	604
MD Elongation (%)	423	482	448
TD @ 5% (g/cm)	231	151	140
TD Ultimate (g/cm)	367	501	440
TD Elongation (%)	410	464	398
Light Transmission (%)	45	43	39
MD Elmendorf Tear (g)	79	195	198

15 While the present invention has been described and illustrated by reference to particular embodiments thereof, it will be appreciated by those of ordinary skill in the art that the invention lends itself to variations not necessarily illustrated herein. For example, it is not beyond the scope of this invention to include additives with the claimed improved, high WVTR film process. For this reason, then, reference should be made to the appended claims and the remainder of the specification for purposes of determining the true scope of the present invention.

**We claim:**

## Claims

1. A process for producing a film having a WVTR greater than  $200 \text{ g/m}^2/\text{day}$  at  $38^\circ\text{C}$  and 90% relative humidity comprising a polyolefin and a filler, said process comprising:
  - a) extruding a precursor film from said polyolefin blend comprising said first and said second polymer compositions and said filler, said filler concentration being in a range of from about 16.5 to about 71.5 wt.%; and
  - b) passing said precursor film between at least one pair of interdigitating grooved rollers, said rollers being maintained in a temperature range of from about  $91^\circ\text{F}$  to about  $159^\circ\text{F}$ , so that said film is heated to produce said film having a WVTR greater than  $200 \text{ g/m}^2/\text{day}$  at  $38^\circ\text{C}$  and 90% relative humidity.
2. The process of claim 1 wherein said polyolefin is selected from the group consisting of polypropylene, polyethylene, ethylene polar comonomer polymers, ethylene  $\alpha$ -olefin copolymers and combinations thereof.
3. The process of claim 1 further comprising cooling said precursor film to a temperature of at least  $75^\circ\text{F}$  or less after step a) but prior to step b).
4. The process of claim 1 wherein said rollers are maintained in a temperature range of from about  $95^\circ\text{F}$  to about  $159^\circ\text{F}$ .
5. A process for producing a film having a WVTR of at least  $200 \text{ g/m}^2/\text{day}$  at  $38^\circ\text{C}$  and 90% relative humidity comprising a polyolefin blend, said polyolefin blend having at least a first and a second polymer composition, and a filler, said process comprising:
  - a) extruding a precursor film from said polyolefin blend comprising said first and said second polymer compositions and said filler, said filler

concentration being in a range of from about 16.5 to about 71.5 wt.%,  
wherein,

- i) said first polymer composition is a polypropylene and
- ii) said second polymer composition is selected from the group  
consisting of elastomers, plastomers, styrenic block copolymers,  
ethylene-maleic anhydride copolymers, ethylene ethyl acetate, and  
combinations thereof; and
- b) passing said precursor film between at least one pair of interdigitating  
grooved rollers so that said film has at least
  - i) a WVTR in a range of from about 200 g/m<sup>2</sup>/day to about 10,000  
g/m<sup>2</sup>/day at 38°C and 90% relative humidity,
  - ii) a dart drop impact in a range of from about 100 grams to about 300  
grams, and
  - iii) an elongation selected from the group consisting of machine  
direction, transverse direction and combinations thereof in a range of  
from about 150% to about 550%.

6. The process of claim 5 wherein said polypropylene is selected from the group  
consisting of random copolymer polypropylene, impact copolymer  
polypropylene, polypropylene produced with a metallocene catalyst and  
combinations thereof.

7. The process of claim 5 wherein said elastomer is selected from the group  
consisting of styrene-isoprene-styrene, styrene-butadiene-styrene, styrene-  
ethylene-butylene-styrene, ethylene alpha-olefin rubber, ethylene propylene  
diene monomer rubber, butyl rubber, vulcanized natural rubber and  
combinations thereof.

8. The process of claim 5 wherein said plastomer is at least one ethylene  $\alpha$ -olefin  
copolymer selected from the group consisting of ethylene  $\alpha$ -olefin copolymers  
wherein the  $\alpha$ -olefin comonomer is selected from the group consisting butene,  
pentene, hexene, and combinations thereof.



- 5 9. The process of claim 5 wherein a non-woven polymeric material is laminated to said precursor film, after step a) but prior to step b), using a lamination means selected from the group consisting of adhesive, heat, ultrasonic radiation and combinations thereof.
- 10 10. The process of claim 5 wherein said interdigitating grooved rollers are positioned in a direction selected from the group consisting of machine direction, transverse direction and combinations thereof.
- 15 11. The process of claim 5 further comprising forming said film of step b) into a fabricated article selected from the group consisting of diapers, adult incontinence devices, surgical apparel, surgical drapes, sports apparel, industrial apparel, house wrap, filtration media and controlled atmosphere packaging.

Fig. 1




Fig. 2





Fig. 3






Fig. 4

(19) World Intellectual Property Organization  
International Bureau



(43) International Publication Date  
23 November 2000 (23.11.2000)

PCT

(10) International Publication Number  
**WO 00/69615 A3**

(51) International Patent Classification<sup>7</sup>: **B29C 55/18**

(21) International Application Number: **PCT/US00/13287**

(22) International Filing Date: **15 May 2000 (15.05.2000)**

(25) Filing Language: **English**

(26) Publication Language: **English**

(30) Priority Data:  
**09/312,103 14 May 1999 (14.05.1999) US**

(71) Applicant: **EXXON CHEMICAL PATENTS, INC.**  
[US/US]; 5200 Bayway Drive, Baytown, TX 77520 (US).

(72) Inventors: **BRADY, Kevin, A.**; 317 Claire Lane, Cary, IL 60013 (US). **MACKAY, John, H.**; 910 Bristol Trail Road, Lake Zurich, IL 60047 (US).

(74) Agent: **ELLIOT, Douglas, H.**; Suite 1500, 3040 Post Oak Boulevard, Houston, TX 77056 (US).

(81) Designated States (*national*): AE, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CR, CU, CZ, DE, DK,

DM, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, TZ, UA, UG, UZ, VN, YU, ZA, ZW.

(84) Designated States (*regional*): ARIPO patent (GH, GM, KE, LS, MW, SD, SL, SZ, TZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).


**Published:**

- With international search report.
- Before the expiration of the time limit for amending the claims and to be republished in the event of receipt of amendments.

(88) Date of publication of the international search report:  
**1 February 2001**

For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

(54) Title: **PROCESS FOR ADJUSTING WVTR AND OTHER PROPERTIES OF A POLYOLEFIN FILM**



(57) Abstract: A process for rendering films, film composites, and articles made therefrom less resistant to passage of water vapor by passing a filled precursor film (10) or film composite through the nip of interdigitating grooved rollers (24, 25). The films (10) or film composites are generally formed using a precursor film (10) of a film forming polyolefin or polyolefin blend, with a relatively high filler loading and optionally an elastomer. A process is disclosed for making diapers or other disposable items where a relatively high water vapor is coupled with a resistance to liquid strikethrough. In one embodiment of the invention, the interdigitating grooved rollers (24, 25) are maintained in a temperature range of from about 91 °F to about 159 °F.

WO 00/69615 A3

# INTERNATIONAL SEARCH REPORT

Intern. Application No  
PCT/US 00/13287

**A. CLASSIFICATION OF SUBJECT MATTER**  
IPC 7 B29C55/18

According to International Patent Classification (IPC) or to both national classification and IPC

## B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC 7 B29C

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

EPO-Internal, WPI Data, RAPRA

## C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	WO 98 04397 A (EXXON CHEMICAL PATENTS INC) 5 February 1998 (1998-02-05) page 14, line 20 - line 22 page 7, line 24 - page 8, line 4 page 11, line 22 - page 12, line 14; example 8; table 3	1-11
A	US 4 289 832 A (SCHWARZ ECKHARD C A) 15 September 1981 (1981-09-15) examples 1,2	1-11
P,X	WO 00 23255 A (EXXON CHEMICAL PATENTS INC) 27 April 2000 (2000-04-27) examples 1-3; table	1-11

☐ Further documents are listed in the continuation of box C.

☒ Patent family members are listed in annex.

### \* Special categories of cited documents :

- \*A\* document defining the general state of the art which is not considered to be of particular relevance
- \*E\* earlier document but published on or after the international filing date
- \*L\* document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)
- \*O\* document referring to an oral disclosure, use, exhibition or other means
- \*P\* document published prior to the international filing date but later than the priority date claimed

\*T\* later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

\*X\* document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

\*Y\* document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art

\*G\* document member of the same patent family

Date of the actual completion of the international search

27 October 2000

Date of mailing of the international search report

28/11/2000

Name and mailing address of the ISA

European Patent Office, P.B. 5818 Patentlaan 2  
NL - 2280 HV Rijswijk  
Tel. (+31-70) 340-2040, Tx. 31 651 epo nl,  
Fax: (+31-70) 340-3016

Authorized officer

Attalia, G

# INTERNATIONAL SEARCH REPORT

information on patent family members

International Application No  
PCT/US 00/13287

Patent document cited in search report		Publication date	Patent family member(s)	Publication date
WO 9804397	A	05-02-1998	AU 3824697 A	20-02-1998
			CA 2260791 A	05-02-1998
			EP 0927096 A	07-07-1999
US 4289832	A	15-09-1981	US 4116892 A	26-09-1978
			US 4153751 A	08-05-1979
			CA 1075870 A	22-04-1980
			DE 2613822 A	14-10-1976
			GB 1521183 A	16-08-1978
			JP 55067052 A	20-05-1980
			JP 51123364 A	28-10-1976
			JP 60026859 B	26-06-1985
			US 4285100 A	25-08-1981
			US 4144008 A	13-03-1979
			US 4223059 A	16-09-1980
			CA 1096117 A	24-02-1981
			DE 2641533 A	31-03-1977
			GB 1521579 A	16-08-1978
			JP 52036166 A	19-03-1977
			CA 1099882 A	28-04-1981
			DE 2812263 A	28-09-1978
			GB 1579718 A	26-11-1980
			JP 53137270 A	30-11-1978
WO 0023255	A	27-04-2000	AU 6429899 A	08-05-2000